

4

10	Providing & laying reinforced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specifications.	Sqm						
			1	400.00	0.90		360.00	
			2	150.00	0.90		270.00	
	Missed Slabs		97	0.60	0.90		52.38	
	Approved Rate of Precast slab	1600.00						
	Data rate for precast slab of 100MM thick						682.38	1600 1091808.00
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 3 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading Item No. 17.1 KSRRB M 100-1 Rs. 62.20 (P.150, I.no.18.57/1, PWD SR							
	Qty Vide Item No 1+2	Cum					325.99	
							325.99	74.07 24147.00
	(For 3 km = 3 x 1.28 x 2.0)	7.68						
	Loading and Unloading Charges	62.20						
		69.88						
	Area Weightage 6%	4.19						
	Total	74.07						
12	Miscellaneous and unforeseen Charges							428
							Total	1950000
(Rupees Nineteen Lakhs Fifty Thousand Only)								

CERTIFICATE

- 1 The Work spot has been inspected and the work found to be necessary
- 2 The Estimate is prepared as per the PWD SR 2013-14
- 3 The Provision made in estimate are adequate and essential
- 4 This area comes under BBMP limits.

[Signature]
Asst Engineer
Ward No-13

[Signature]
Asst Executive Engineer
Shettyhalli Sub-Division
BBMP

[Signature]
Executive Engineer
Dasarahalli Zone
BBMP

A/S
JC(DH) 175248/13-14 30/10/13
19.50 lakhs (Rupees Nineteen
Lakhs fifty thousand only)
Page no. 231
2188

E.E/D.D/T.5/185/13-14 30/10/13
da. 19.50 lakhs
Nineteen lakhs fifty thousand only
P. NO -32